

NOTES:

-dimensions should always be read.DO NOT SCALE. Contractor to cross check all dimensions and report any descrepancy to the Architect before work is commenced. -all dimensions are in millimetres unless otherwise stated -Permanent ventilation (pv) to be provided over all openings except bathroom doors.

-all manhole covers in the drive and parking to be provided with heavy duty and air tight covers.
-all drain pipes under building,parking and driveway to be encased into 150mm thick concrete. -all rc works to structural engineer's detail. -Electrical works to be done by a qualified technician and to be done in accordance with KPLCo. regulations

-Mechanical work to MoH and Local Authority's regulations and specifications. -Water meter to be 300mm minimum above ground level.

-Provide DPC under all walls at ground floor level. -Provide 1000 gauge polythene DPM under ground floor conc floor slab

-S.V.P. to be provided on all stack pipes.

FIRE NOTES (Applicable in office, ware houses and godown\$)

1] Provide 4,500 Litres of water with booster pump. 2] Provide 30metres long horse reel on each floor 3] Provide 1x9 Litres water CO2 Fire Extinguisher at each fire point

4] Provide manual/electrical fire alarm system

5] Provide emergency lighting with independent power systems

PROPOSED KISII CANCER CENTRE IN KENYA

FINANCIERS:

ARAB BANK FOR ECONOMIC DEVELOPMENT IN

SAUDI FUND DEVELOPMENT





REPUBLIC OF KENYA

KISII COUNTY GOVERNMENT





SCHON & ASSOCIATES

NARCO ENGINEERING **CONSULTANTS**





DRAWING TITLE:

MAIN BUILDING FIRST FLOOR PLAN

NOVEMBER 2020 CHECKED: APPROVED:

DRAWING NUMBER:

30.11.2020